

Planting style suitable for childrens' playgrounds

WORRALL STREET

BERYL STREET (GRAVEL)

HULL ROAD

ALWYN STREET

"SILVER BIRCHES"
DOUBLE STOREY
REND. BRICK BUILDING

SINGLE STOREY
W/BD BUILDING

WYREENA
COMMUNITY
ARTS CENTRE
DOUBLE STOREY
BRICK BUILDING

"RADIO
EASTERN"
SINGLE STOREY
BRICK BUILDING

W/BD SHED

Existing Playground (mulched)

Existing synthetic turf

Existing courtyard to be extended

Community centre additions (refer building plans)

Existing pebblecrete path

Proposed pebblecrete path

Existing concrete path

Proposed concrete path

Existing timber walkway

Existing brick walkway

Existing timber seating

Existing recycled plastic flooring

Existing bitumen driveway with paved edge

Existing bitumen driveway

Proposed gravel path (reduction to existing driveway)

Existing gravel path

Proposed gravel drop-off area

Existing concrete with table and chairs

Existing feature rocks

Existing lawn

Existing garden

Existing garden to be retained

Existing garden to be removed

Existing mulched playground

Existing mixed vegetation to be retained

Existing tree to be removed

Existing trees to be retained

Existing mulched playground
Existing synthetic turf

Paving

Exposed aggregate concrete

Gravel

Bitumen

Existing mixed vegetation to be retained

Existing tree to be retained

Tree protection zone

Proposed trees

Lawn

Mulched garden

Feature avenue trees such as crepe myrtles, *Lagerstroemia indica 'Tuscarora'* with a triple tier of formal plantings including *Pittosporum 'Golf Ball', Nandina domestica 'Blush'* and *Rhaphiolepis indica 'Oriental Pearl'*.

Feature tree such as *Populus 'Raywood'*, underplanted with Liriope

Convert existing grass to native garden

Lush screen planting of *Backhousia citriodora* underplanted with native grasses, *Westringia mundi, Callistemons* and spreading *Correas*

Existing native planting to be retained

Convert existing grass to native garden

Eroded site cut to be repaired, planted and protected as per embankment specification below.

Large, eroded site cut to be repaired, planted and protected as per embankment specification below. Provide new timber boardwalk and steps to create a pathway.

Plant additional Silver Birch trees to create a grove with massed planting of daffodils and silver coloured ground cover planting below and stepping pad paths through as show.

Remove existing weed species adjacent to the area where new carparks are to be constructed. Install relocatable brush fence screens to protect the privacy of neighbouring properties until new screen planting is established. Retain native trees and shrubs.

Remove existing weed species adjacent to the area where new carparks are to be constructed. Install relocatable brush fence screens to protect the privacy of neighbouring properties until new screen planting is established. Retain native trees and shrubs.

Retain existing Lomandra border along ~~Parking space~~. Removal of weed species that are providing privacy to neighbouring properties to take place as a third stage, following establishment of the replacement screen planting to the north. Temporary brush fence screening panels to be relocated here to provide privacy screening while waiting for new native tree and shrub planting to establish.

Removal of weed species that are providing privacy to neighbouring properties to take place as a third stage, following establishment of the replacement screen planting to the north. Temporary brush fence screening panels to be relocated here to provide privacy screening while waiting for new native tree and shrub planting to establish.

Removal of weed species that are providing privacy to neighbouring properties to take place as a second stage, following establishment of the replacement screen planting to the north. Temporary brush fence screening panels to be relocated here to provide privacy screening while waiting for new native tree and shrub planting to establish.

Removal of weed species that are providing privacy to neighbouring properties to take place as a third stage, following establishment of the replacement screen planting to the north. Temporary brush fence screening panels to be relocated here to provide privacy screening while waiting for new native tree and shrub planting to establish.

Remove existing weed species adjacent to the area where new carparks are to be constructed. Install relocatable brush fence screens to protect the privacy of neighbouring properties until new screen planting is established. Retain native trees and shrubs.



Silver birch grove with daffodil underplanting



Temporary brush fence to provide screening as each section of the street facade is renovated



Example of the style of planting proposed for screening along Alwyn Street



Example of the style of native planting proposed for the garden beds along Beryl Street and extending east of the carpark



Example of the lush style of garden proposed for the central area, around tree 49 and north of the Wyreena Community Arts Centre

Outward Design
ph: 9776 6003
scapes@outwarddesign.com.au
PO Box 815, Somerville VIC 3912
outwarddesign.com.au

project: Wyreena Community Centre

scale: 1:250 @ A1

date: 19th June 2018

amend: 10th December 2018

drawing no: TV18051

OUTWARD DESIGN
LANDSCAPE DESIGNERS